



BOROUGH OF NEW MILFORD  
BUREAU OF CODE ENFORCEMENT  
PLANNING AND ZONING

James L. Taormina  
Construction Official  
Building Sub Code Official

Maria Sapuppo  
Zoning Officer  
Certified Technical Assistant  
Planning Board Secretary

Maureen Oppelaar  
Certified Technical Assistant  
Zoning Board of Adjustment Secretary

**Pool Demolition /Fill In**

The demolition or fill in of any pool (both concrete & vinyl lined) requires a Construction Permit issued by this Department prior to starting the work.

1. It is required that all concrete be broken up into pieces no larger than 8" inches to minimize air voids if it is intended to be mixed in with the clean fill, bank run, etc. then add 1 layer of stone/ gravel, fill of dirt.
2. All steel reinforcement must be removed.
3. All vinyl liner material must be removed.
4. Large pieces of concrete and steel must be removed from the site and are not permitted for backfill.
5. Any in-ground piping for the filtration system or used for filling the pool must be removed. Any in-ground wiring or electrical conduits for lighting, filtration, etc. must be removed. Any in-ground gas piping for pool heater must be removed.
6. Only clean fill can be used and a minimum of 6" inches of topsoil must cover the surface to be brought back to grade. Compaction of 95% of fill material is recommended to minimize settling.

**Required Inspections**

1. Backfill – Prior to filling excavation to check for removal of materials per above. All clean fill material must be on site for inspection.
2. Final - Work completed, job site free of debris, graded and seeded.

